

सिंचाई विभाग, उत्तराखण्ड



अपार शक्तेः स्त्रौतः गंगेयम

सिंचाई बढ़ाएं खुशहाली लाएं।

योजना का नाम - : जनपद पिथौरागढ़ के धारचूला विकास खण्ड में काली नदी के दॉये पार्श्व में स्थित आर्मी कैम्प-1 की काली नदी से सुरक्षा हेतु बाढ़ सुरक्षा योजना।

अनुमानित लागत : रु0 2451.07 लाख

वर्ष : 2024-25

सिंचाई कार्य मण्डल, पिथौरागढ़।

सिंचाई खण्ड, धारचूला।

कार्यालय मुख्य अभियन्ता (स्तर-11)
सिंचाई विभाग, उत्तराखण्ड, अल्मोड़ा

पत्रांक:- 1252 / मु0अ0(स्तर-11) / ई-14 /

दिनांक:- 11.06.2024

-:कार्यालय ज्ञाप:-

जनपद पिथौरागढ़ के धारचूला विकास खण्ड में काली नदी के दोंये पार्श्व में स्थित आर्मी कैम्प-1 की काली नदी से सुरक्षा हेतु बाढ़ सुरक्षा योजना लागत रु0 2451.07 लाख (रु0 चौबीस करोड़ इक्यावन लाख सात हजार मात्र) को लेखाशीर्षक 8443 डिपोजिट मद के अन्तर्गत तकनीकी स्वीकृति निम्न प्रतिबन्धों के साथ एतद्वारा प्रदान की जाती है।

01. योजना के क्रियान्वयन के समय डिपोजिट मद की गाईड लाईन व निदिष्टियों का पालन करते हुए आवंटित बजट का उपयोग भारतीय सैन्य विभाग के पत्र सं0 1189/Kali River Dated 06.03.2024 के अनुसार किया जाये।
02. स्वीकृति योजना में प्राविधानित राशि से किसी भी दशा में व्ययाधिक्य न हो।
03. स्वीकृति योजना के स्वरूप में किसी भी प्रकार के फेरबदल से पहले आवश्यक स्वीकृति प्राप्त कर लें।
04. कार्य की गुणवत्ता एवं समयबद्धता हेतु संबंधित अधिशासी अभियन्ता पूर्ण उत्तरदायी होंगे।
05. योजना में ली गई कार्यों की दरों हेतु सम्बन्धित अधीक्षण अभियन्ता उत्तरदायी होंगे।

उपरोक्त स्वीकृति इस कार्यालय के प्राक्कलन पत्रिका के क्रमांक- 04/सीई(स्तर-11)/वर्ष 2024-25 में पंजीकृत की जाती है।

(चन्द्रशेखर सिंह)
मुख्य अभियन्ता(स्तर-2)

पत्रांक:- 1252 / मु0अ0(स्तर-11) / ई-14 /

तददिनांक।

प्रतिलिपि निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित:-

01. महालेखाकार लेखा एवं हकदारी महालेखाकार भवन, पो0 आफिस-सब पोस्ट मॉस्टर पेट्रोलियम संस्थान कौलागढ़, जिला-देहरादून।
02. प्रमुख अभियन्ता (बजट अनुभाग) माधो सिंह भण्डारी भवन, सिंचाई विभाग उत्तराखण्ड, देहरादून।
03. अधीक्षण अभियन्ता, सिंचाई कार्य मण्डल, पिथौरागढ़ को उनके पत्रांक:- 1674/सिकामपि/पी-2 प्राक्कलन दिनांक: 31.05.2024 के सन्दर्भ में स्वीकृत योजना की प्रति सहित अग्रिम आवश्यक कार्यवाही हेतु प्रेषित है।
04. अधिशासी अभियन्ता, सिंचाई खण्ड धारचूला को स्वीकृत योजना की प्रति सहित अग्रिम आवश्यक कार्यवाही हेतु प्रेषित है।
05. पत्रावली हेतु।

(चन्द्रशेखर सिंह)
मुख्य अभियन्ता(स्तर-2)

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT
ARMY CAMP -1 IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH

INDEX

Sl. No.	Details	Page Nos
1	Checklist	
2	Recommendation	
3	Report	
4	Drill Proforma	
5	Certificate of S.E.	
6	Salient Features	
7	Hydrology and design	
8	Statement I showing Damages and Relief Measures before completion of Scheme	
9	Statement II showing Damages and Relief Measures after completion of Scheme	
10	Statement III showing Benefit/Cost Ratio	
11	General Abstract of Cost	
12	O- Miscellaneous	
13	Abstract of Cost	
14	Abstract of Quantity	
15	Analysis of Rates	
16	Statement showing probable losses / damages of properties	
17	Drawing	
	a. Index map	
	b. Plan & Section Of Proposal	

IRRIGATION DIVISION DHARCHULA

**FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY
CAMP -I IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH**

Check List for Preliminary Examination of Flood Protection/Anti-erosion Schemes

S.N.	Particulars	YES/NO
1	Has the Scheme formulated in accordance with instructions/guidelines issued so far by G.F.C.C. and T.A.C.?	Yes
2	Has the topsheet prepared by Survey of India, showing the catchment area of the river/nala at scheme site, been enclosed? If not, why?	Yes
3	Have the following information/data been furnished and discussed in the Detailed Project Report?	
	(a) Flood Frequency for which the scheme has been designed.	50 Years
	(b) Broad discussions of the problem comprising history of past floods, frequency, hydrology of the stream, tendency of flow, mode of observation of gauge/discharge and works executed in the past with their results obtained.	Yes
	(c) Inspection details of the area affected/protected, any scheme in progress or proposed in vicinity.	Yes
	(d) General discussions on viable alternatives and justification for adopting this proposal out of them.	Yes
	(e) Basis of criteria/rates adopted for evaluating the property damaged/protected to arrive at Benefit Cost ratio duly supported by flood damage data for past ten years, duly certified by revenue.	Yes
	(f) Surveys conducted in formulation of the scheme with description of designed features.	Yes
	(g) Construction Programme.	Yes
	(h) Recommendations.	Yes
4	Have the Index map and layout plan to scale, showing past flood bank line, contours and spot levels, (with reference to level book, surveyed by, date of survey, bench marks etc.) area affected and layout of proposed work duly approved been enclosed?	Yes
5	Have the L-Section and X-Sections of the river/nala at suitable intervals indicating bed levels, G.L., formation level, hydraulic gradients, design H.F.L. (with reference to level book etc.) duly approved been enclosed?	Yes
6	Have the Designs/working drawings, supported by design calculations, duly approved been enclosed?	Yes
7	Has the scheme formulated after superimposing on Satellite imageries maps? If not why?	Yes
8	Has the surveys conducted with latest digital method?	Yes
9	Whether silt factor has been worked out/examined by I.R.I., Roorkee? If Yes, mention in full, if not quote reason.	Yes
10	Have the gauge/discharge sites been established to observe actual discharge? Are calculations for design flood enclosed?	No
11	Whether this project is original or revised? If revised, quote reason for revising it with previous references.	Original
12	Whether free board is kept as per actual water depth or as per BIS Code? Mention Water depth/BIS Code as the case may be.	Actual Water Depth
13	Are the sizes of proposed C.C. blocks, wire crates and boulders in abutment pitching as per BIS Code? Mention respective Code No.	Yes
14	Is it an Inter-State scheme? If so, has the concurrence of the concerned authority obtained and discussed in the project?	No
15	Has the concurrence from the departments like Railways, National Highways, Forests, etc. been obtained, if they are affected?	No
16	Are individual detailed reports by D.E., S.E. and C.E. enclosed?	Yes


A.E.R.

Adhoc Station Headquarters
Dharchula
c/o KUMAON SCOUTS
PIN - 911 300
c/o 56 APO

1189/Kali River

06 Mar 2024

Irrigation Dept, Dharchula

COMMENCEMENT OF DEPOSIT WORK AT MILITARY STATION DHARCHULA

1. Please refer MoU between Ministry of Defence through the Station Headquarter, Dharchula and SE Pithoragarh through Irrigation Dept Dharchula.
2. Rs 16,88,58,200/- (Rupees sixteen crores eighty eight lakhs fifty eight thousand two hundred only) out of Rs 33 Crores (40% of the first instalment of agreed amount) has been cleared by CDA (Army), Meerut & ready to be transferred to your account. This Headquarter has taken up a case for credit of balance of amount also i.e Rs 16,11,41,800/- (Rupees sixteen crores eleven lakhs forty one thousand eight hundred only). The same will also be credited into your account on receipt.
3. You are requested to share the bank details (Account No, IFSC & MICR No) directly with GE (MES), Pithoragarh so that the amount can be transferred into the account.
4. An early action is requested pl.




(Gita Nand)
Maj
SSO
for Stn Cdr

Copy to :-

HQ Central Comd (Q)
HQ UB Area (Q)
HQ UK Sub Area (Q)
HQ 119 (I) Inf Bde Gp (Q)
CWE (Hills), Pithoragarh
GE (MES) & AO GE (MES), Pithoragarh
AGE (MES), Dharchula

for info pl.

Adhoc Station Headquarters
Dharchula
c/o KUMAON SCOUTS
PIN - 911 300
c/o 56 APO

1189/Kali River

09 Mar 2024

Executive Engineer
Irrigation Dept, Dharchula
Pithoragarh

REGARDING EXECUTION OF FLOOD PROTECTION WORKS AT MILITARY ESTABLISHMENTS SITUATED AT RIGHT BANK OF KALI RIVER IN DHARCHULA BLOCK DISTRICT-PITHORAGARH

1. It is intimated that Rs 33 Cr (40% of the total amount) was transferred to carry out flood protection work at following locations as deposit work. The project wise allocation of funds is as under :-

<u>S No</u>	<u>Location</u>	<u>Estimate cost (in Lacs)</u>	<u>40% of Cost transfer</u>
(a)	Army Camp-2 Battalion campus Galati	4060.10	15.47 Cr
(b)	Army Camp-1	2451.07	9.804 Cr
(c)	Army camp-2 family campus Tallahaat	1600.13	6.40 Cr
(d)	Army camp-2 family campus Mallahaat	331.61	1.326 Cr

2. Keeping in view the urgency of above works, you are requested to take appropriate action at your end to get the above works done as early as possible for the protection of military area land to complete the above projects within stipulated time.
3. You are also requested to intimate the present status of the tender action and tentative date on which work at above four location is going to commence.
4. Above details are required to be forward to the higher formation for their perusal. Hence, the same be intimated at the earliest.


(Gita Nand)
Maj
SSO
for Stn Cdr

Copy to :-

HQ UK Sub Area (Q) }
HQ 119 (I) Inf Bde Gp (Q) } - for info pl.

सिंचाई कार्यमण्डल पिथौरागढ़।
सिंचाई खण्ड, धारचूला।

योजना का नाम - जनपद पिथौरागढ़ के धारचूला विकास खण्ड में काली नदी के बाँये पार्व में स्थित आर्मी कैम्प-1 की काली नदी से सुरक्षा हेतु बाढ़ सुरक्षा योजना।

आख्या

जनपद पिथौरागढ़ उत्तराखण्ड राज्य का सीमांत एवं पर्वतीय जनपद है। इसका भौगोलिक क्षेत्रफल 7218 वर्ग किमी० है। इस जनपद की पूर्वी सीमा नेपाल से मिलती है। जनपद की पूर्वी सीमा पर बहने वाली काली नदी भारत-नेपाल सीमा का निर्धारण करती है। नदी के पूर्वी तीरे पर नेपाल सीमा स्थित है। नदी का उपग्राम क्षेत्र हिमालय है।

वर्ष 2016-17 में नेपाल सरकार द्वारा काली नदी के बाँये पार्व पर नेपाल राष्ट्र की ओर धारचूला से गन्ताही तक दार्चुला ग्राम में लगभग 5 किमी० लम्बाई में आर०सी०सी० फाईट द्वारा निर्मित सुरक्षा दीवार, दीवार के पीछे सड़क एवं दीवार के आगे एबन एवं अतिरिक्त ब्लॉक (छोटे पत्थर) का निर्माण कार्य करवाया गया। एवं जीवजीवी से नुंजी तक अपनी ओर (नेपाल राष्ट्र की ओर) बसाने एवं भूमि बचाने हेतु अन्य स्थानों में बायर कंट के स्पर बनाये गये हैं। जिससे नदी का रुख भारतीय तट की ओर स्थित ग्रामों, भारतीय सुरक्षा विभाग, भारतीय सैन्य बलों के ईकाई एवं पूर्व में बनी सुरक्षा दीवारों की ओर हो गया है। कई स्थानों पर मानसून अवधि के दौरान भू-कटाव हुआ है। वर्तमान में साधान्य जन, जनप्रतिनिधियों एवं भारतीय सुरक्षा विभाग, भारतीय सैन्य बलों के द्वारा काली नदी के किनारे भारतीय तट के ग्रामों एवं भूमि को नदी के कटाव से बचाये जाने हेतु सुरक्षात्मक कार्य करवाये जाने हेतु बार-बार अनुरोध किया जा रहा है। जिससे भारतीय तट पर मानसून अवधि में काली नदी के किनारे स्थित सगनों एवं भूमि को नदी के तीव्र कटाव से सुरक्षा प्रदान की जा सके। दिनांक 28.10.2020 एवं 29.10.2020 को सिंचाई विभाग एवं भारतीय सुरक्षा विभाग द्वारा काली नदी के किनारे नेपाल राष्ट्र द्वारा किये गये कार्यों का स्थलीय निरीक्षण किया गया। निरीक्षण के दौरान भारतीय तट को सुरक्षा प्रदान किये जाने हेतु धारचूला व भारतीय सैन्य बलों के ईकाई, सैन्य परिषद की सुरक्षा हेतु बाढ़ सुरक्षा कार्य किया जाना अति आवश्यक है। यह कार्य अवहित में कराया जाना आवश्यक है। उक्त परिषद की बाढ़ सुरक्षा कार्य सम्पादनार्थ हेतु भारतीय सैन्य विभाग द्वारा अपने पत्र 1189/Kali River Dated 06.03.2024 के माध्यम से उक्त बाढ़ सुरक्षा कार्य के सम्पन्न की वित्तीय स्वीकृति भी प्रदान किया गया है।

प्रस्तावित कार्य :-


काली नदी के बाँये तट पर कुल 500.00 मी० लम्बाई में सी०सी० में 8.50 मी. ऊंची पक्की दीवार का निर्माण प्रस्तावित है। सुरक्षा दीवार के आगे मध्य से मध्य 15 मी० दूरी पर सी०सी० एम००२० के स्टड ब्लॉक का प्राविधान किया गया है।


लाभ लागत :-


इस योजना के निर्माण से 80 भवनों एवं 115 हेक्टेर की भूमि का बचाव हो सकेगा तथा लगभग 580 जनसंख्या लाभान्वित होगी। योजना की कुल लागत रु० 2451.07 लाख तथा योजना का लाभ-लागत अनुपात 1.40: 1 है।

संस्तुति :-

उक्त वर्णित बिन्दुओं से स्पष्ट है कि योजना अत्यन्त लाभप्रद एवं धारचूला में भारतीय सैन्य बलों के ईकाई, सैन्य परिषद की सुरक्षा महत्वपूर्ण है। भारतीय सैन्य विभाग द्वारा भी पथावश्यक कार्यवाही हेतु मांग की गई है। अतः उक्त के दृष्टिगत प्रस्तुत योजना सगनों की स्वीकृति हेतु प्रबन्ध संस्तुति सहित प्रेषित है।


सहायक अभियन्ता-।
सिंचाई खण्ड, धारचूला।


अधिरासी अभियन्ता
सिंचाई खण्ड, धारचूला।


अधीक्षण अभियन्ता
सिंचाई कार्यमण्डल पिथौरागढ़।

IRRIGATION DIVISION DHARCHULA

**FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY
CAMP -1 IN BLOCK DHARCHULA .DISTRICT PITHORAGARH**

CERTIFICATE TO BE FURNISHED BY THE SUPERINTENDING ENGINEER

Certified that :

- | | |
|--|-----|
| 1 The report of the Superintending Engineer (duly signed) has been enclosed | Yes |
| 2 The report of the Chief Engineer concerned has been enclosed | Yes |
| 3 The drawings have been signed by the Superintending Engineer. | Yes |
| 4 The Drill Performa has been enclosed and signed by the Superintending Engineer and the Executive Engineer | Yes |
| 5 The project estimates have been checked by the Computer of the circle and signed by him | Yes |
| 6 The survey maps, L-Section, X-Section giving the levels bear the certificate of the Junior Engineer that the Survey has been done by Private Surveyer and the place and the levels of the starting Bench Mark and closing Bench Mark have been recorded. | Yes |
| 7 The certificates of the Assistant Engineer to the effect that he supervised the surveys carried out by the Private Surveyer and that he is fully satisfied about their correctness, is enclosed. | Yes |



**Superintending Engineer
IWC Pithoragarh**

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH

DRILL PERFORMA

- | | |
|---|---|
| 1 Name of the Project Estimate | Flood Protection Work Along Right Bank Of Kali River At Army Camp -1 In Block Dharchula ,District Pithoragarh |
| 2 Estimate amount and head of account | Rs. 2451.07 Lacs
4711 Capital Outlay on Constructing Flood Protection Works |
| 3 Has the work been started in anticipation of sanction of the estimate and if so, under what authority? The date of starting the work along with the reasons for doing so and whether the A.G. has been informed | No. |
| 4 Date of completion if the work has already been completed if not the stage of progress of work. | Questions does not arises. |
| 5 Is the estimate based on figures of expenditure as actually incurred, if completed | No. |
| 6. i Name of the project head and subhead of the project estimate showing the amount provided for | 4711 Capital Outlay on Constructing Flood Protection works Rs.2451.07 Lacs |
| ii Total amount of estimate already sanctioned in subhead by Chief Engineer & Superintending Engineer | Nil |
| iii Total amount of liabilities already incurred against unsanctioned estimate and anticipated excess over sanctioned estimate | Nil |
| iv The Total amount of further estimate proposed to be sanctioned in the sub-head | Nil |
| v Can the estimate be met out of saving in the sub-head, if not how is the excess, proposed to be met. | Not applicable |
| 7 Have the drawing been approved and signed by the Chief Engineer/Superintending Engineer | Yes signed by Superintending engineer |
| 8 Has the L-section submitted with estimate been approved by the Chief Engineer | Not required |

9 Have the analysis of rates been prepared in accordance with standard laid down in Chief Engineer office Memo No. 2825-VI, dated May, 3 1961 and subsequent amendment thereof and are the labour rates adopted in conformity with the sanctioned schedule of labour rates of Divisional/Circle?

Yes

10 Are the rates adopted for earth work by machines in accordance with the latest instructions issued by the Chief Engineer, and where these do not apply in accordance with the recommendations of the rates and cost committee, full justification be given?

No earth work is to be done by machine

11 If the rates provided are the tendered rates, have these rates been mentioned below the rates worked out on the basis of prescribed standard analysis of rates that will be cost of work on the basis of the standard rates been together have full reasons been given in this project?


No tender has been invited so far. The estimate has been prepared on the basis of sanctioned schedule of rates and current market rates.


12 Project has been carefully checked and certificate of check recorded thereon of your computer.

Yes

13 Are you satisfied that all the design quantities and rates are in the order and conform to the principle of safety and economy and the work so constructed fulfill the purpose for which they are proposed? Have you appended detail rates on the estimates embodying your views on these points.

Yes


Executive Engineer
Irrigation Division Dharchula



Superintending Engineer
IWC Pithoragarh


IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1
IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH

SALIENT FEATURES OF FLOOD PROTECTION SCHEME

1 Name of Scheme	FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH
2 District	Pithoragarh
3 River and Bank	Kali River & Right Bank
4 a. Area affected	11.5 Ha
b. Area benefited	11.5 Ha
5 a. House & Property damaged	80 Houses , Rs. 1300 Lacs
b. House & Property benefited	80 Houses , Rs. 1300 Lacs
6 a. Population affected	580.00
b. Population benefited	580.00
8 Hydrology	
a. Design discharge	4244 Cumecs
b. Maximum observed H.F.L.	5.00 M
c. Design H.F.L.	5.00 M
9 Proposals	
Length	580 m
Main Work to be done under this Scheme	CC Wall- Foundation 10.0x 5.0 x2.0 m(M20),P/Wall 10.0 x(5.0+0.6)/2 X6.5 Apron Block-6.25x6.75x1.5 m (M15) Additional Block-5.5x5.75x2.0m (M15) @ 20 m C/C
10 Cost of scheme	Rs. 2451.07 Lacs
11 Benefit Cost Ratio	1.4:1


Assistant Engineer
I.D. Dharchula



Executive Engineer
I.D. Dharchula


IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN
BLOCK DHARCHULA, DISTRICT PITHORAGARH

STATEMENT - I: SHOWING DAMAGES AND RELIEF MEASURES
BEFORE COMPLETION OF SCHEME

Name of River	Kali River
Name of Scheme	FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK DHARCHULA, DISTRICT PITHORAGARH
1 Nature of Flood	
i) Year	Every Year
ii) Area affected	11.50
iii) Frequency of flood	Every Year
iv) Duration of inundation	Nil
v) Probable death of inundation	Nil
2 Damages	
<i>a) Land and Crops</i>	
i) Area of inundation	Nil
ii) Value of crops	Nil
iii) Area eroded	11.5
iv) Value of land	Rs. 5520 Lacs
<i>b) Damages of House</i>	
i) Nos.	80.00
ii) Value	Rs. 1300 Lacs
iii) Loss of human life	Nil
<i>c) Cattle Loss</i>	
i) Nos.	Nil
ii) Values	Nil
<i>d) Damages to Public Utility</i>	Nil
Total Damages	Rs. 6820 Lacs
3 Relief Measures	
i) Gratuitous relief	Nil
ii) Agriculture	Nil
iii) Remission of land revenue	Nil
iv) Other relief measures	Nil
Total Relief Expenditure	Nil
4 Total cost of relief and damages	Rs. 6820 Lacs
5 Extent of beneficial value fertilising silt.	Nil
6 Net annual flood losses	Rs. 547.45 Lacs


Assistant Engineer
I.D. Dharchula



Executive Engineer
I.D. Dharchula

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -I IN
BLOCK DHARCHULA ,DISTRICT PITHORAGARH

STATEMENT-II OF FLOOD DAMAGES AND RELIEF MEASURES AFTER COMPLETION OF THE
SCHEME

- | | | |
|---|---|--------------|
| 1- Name of Project | FLOOD PROTECTION WORK ALONG RIGHT BANK
OF KALI RIVER AT ARMY CAMP -I IN BLOCK
DHARCHULA ,DISTRICT PITHORAGARH | |
| 2- Name of River | Kali River | |
| 3- Area protected by the scheme | | |
| (a)-Houses | 80 | Nos (Approx) |
| (b)-Land | 11.5 | Ha |
| 4- Population protected by the scheme | 580.00 | Nos (Approx) |
| 5- Annual flood losses after completion of the scheme | No damages expected after completion of the scheme | |
| 6- Population likely to be still affected | NiL | |
| 7- Frequency of flood | Every year in rainy season | |
| 8- Depth of inundation in m | NiL | |
| 9- Damages to crops | NiL | |
| 10- Total damages in lacs | NiL | |
| 11- Indicate approximate estimate of probable expenditure that may still be necessary | NiL | |
| 12- Net amount of flood losses | NiL | |


Assistant Engineer
I.D. Dharchula


Executive Engineer
I.D. Dharchula

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN
BLOCK DHARCHULA ,DISTRICT PITHORAGARH

STATEMENT III BENEFIT-COST ANALYSIS

I Name of Project FLOOD PROTECTION WORK ALONG RIGHT BANK
OF KALI RIVER AT ARMY CAMP -1 IN BLOCK
DHARCHULA ,DISTRICT PITHORAGARH

i) Net annual losses due to flood	Rs	547.45	Lacs
ii) Net annual losses after completion of the scheme		NIL	
II Cost			
a) Cost of Scheme	Rs	2451.07	Lacs
b) Cost of existing works		NIL	
c) Annual interest payable @ 10% on capital cost	Rs	245.11	Lacs
d) Annual depreciation @ 2% on capital cost	Rs	49.02	Lacs
e) Requiring annual maintenance charges @ 4% on capital cost	Rs	98.04	Lacs
	Total	Rs	392.17 Lacs

Benefit Cost Ratio = $\frac{547.45}{392.17} = 1.40 : 1$


Assistant Engineer
I.D. Dharchula


Executive Engineer
I.D. Dharchula


✓

IRRIGATION DIVISION DHARCHULA

**FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN
BLOCK DHARCHULA ,DISTRICT PITHORAGARH**

STATEMENT OF AVERAGE ANNUAL LOSSES FOR THE YEAR 2022-23

1a. Agricultural Area endangered by erosion by kali River		0.0	Ha
1b Non Agricultural Area endangered by erosion by kali River		11.5	Ha
1c Cost per ha for Agricultural Land	Rs	363.0	Lacs
1d Cost per ha for Non Agricultural Land	Rs	480.0	Lacs
2a Pucca Houses endangered by erosion by kali River		50	Nos
2b Kachcha Houses endangered by erosion by kali River		30	Nos
2c Cost per Pucca Houses	Rs	20	Lacs
2c Cost per Kachcha Houses	Rs	10	Lacs
3a Cost of 0Ha Agricultural Land	Rs	0.00	Lacs
3b Cost of 11.5Ha Non Agricultural Land	Rs	4174.50	Lacs
4 Cost of houses			
a) Cost of Pucca Houses	Rs	1000.00	Lacs
b) Cost of Kachcha Houses	Rs	300.00	Lacs
	Total	Rs 5474.50	Lacs
5 Net average losses due to erosion assuming 10 years period	Rs	5474.50	Lacs
6 Average annual losses	Rs	547.45	Lacs


Assistant Engineer
I.D. Dharchula



Executive Engineer
I.D. Dharchula


IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -I IN
BLOCK DHARCHULA ,DISTRICT PITHORAGARH

ABSTRACT OF COST OF PROJECT

1	कार्य की लागत	रु 2451.07 लाख
2	अप्रत्यक्ष व्यय	
	(अ) अधिष्ठान पर व्यय	-
	(ब) यंत्र संयंत्र पर व्यय	-
3	प्रत्यक्ष व्यय	
	(अ)आडिट एवं एकाउन्ट पर व्यय	-
	सम्पूर्ण योग	रु 2451.07 लाख


सहायक अभियन्ता-।
सिंचाई खण्ड, धारचूला।


अधिसास अभियन्ता
सिंचाई खण्ड, धारचूला।

IRRIGATION DIVISION DHARCHULA
FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK
DHARCHULA, DISTRICT PITHORAGARH

Calculation Of Discharge & Scour Depth

1	Catchment Area	(A)	=	2330.00 Sq. km
2	Slit factor	(f)	=	10.40
3	Rugosity coefficient of channel	(n)	=	0.025
4	Slope of channel (S)	(S)	=	17.827 M/Km
5	Bed Width	(B)	=	60.00 m
6	Water Depth	(D)	=	5.00 m
7	Free Board	(fb)	=	1.50 m
National Institute of Hydrology-				
8	Return Period	(T)	=	25.00
9	Coefficient for 25 Year return Period	(C)	=	$C = [- \frac{5.654 + 10.724 \{1/(T-1)\} - 165}{T}]$ = 12.46
10	Peak flood discharge	(Q)	=	$C(A)^{0.771}$ = 4918.74 Cumec
Design discharge By Dicken's Method :				
11	Return Period	(T)	=	50.00 Year
12	constant, for North Indian rivers	(C)	=	11.40
13	Design Discharge	(Q)	=	$C(A)^{0.771}$ = 3823.15 Cumec
By Area Velocity Method:				
14	Area	(A')	=	$B \times D$ = 300.000 Sqm
15	Wetted Perimeter	(P)	=	$B + 2D$ = 70.000 m
16	Hydraulic Depth	(R)	=	A'/P = 4.286
17	(R)%	(R)%	=	2.639
18	(S)%	(S)%	=	0.134
19	Discharge	(Q)	=	$A' \times (R)^{0.54} \times (S)^{0.74} / n$ = 4243.51 Cumec
20	Velocity	(V)	=	Q/A' = 14.15 m/Sec
21	Adopted Discharge	(Q)	=	4244.00 Cumecs
Design of Scour Depth:				
22	Lacey Wetted Perimeter	(Placey)	=	$4.75(Q)^{1/3}$ = 309.44 m
		(Placey)	>	(P)
23	Thus discharge intensity per metre bed width of river	(q)	=	Q/B = 70.73 Cumec /m
24	Scour depth	(R)	=	$1.35 \times (q^2/f)^{1/3}$ = 10.58 m
In Straight Reach:				
25	Taking 1.25 times of R, Scouring depth below H.F.L.	(D1)	=	$1.25 \times R$ = 13.23 m
26	Depth of Scour below Bed level	(D2)	=	$D1 - D$ = 8.23 m
In Curved Reach:				
27	Taking 1.50 times of R, Scouring depth below H.F.L.	(D1)	=	$1.50 \times R$ = 15.87 m
28	Depth of Scour below Bed level	(D2)	=	$D1 - D$ = 10.87 m

IRRIGATION DIVISION DHARCHULA
FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN
BLOCK DHARCHULA ,DISTRICT PITHORAGARH

Calculation For Height of Wall

1	Water Depth	(D) =	5.00 m
2	Depth of Scour below Bed level (Straight Reach)	(D2) =	8.23 m
3	Take Scour Depth of Wall	(h1) =	2.00 m
4	Free Board	(h) =	1.50 m
5	Total Height of Wall	(H) =	8.50 m



Assistant Engineer
Irrigation Division Dharchula



Executive Engineer
Irrigation Division Dharchula

IRRIGATION DIVISION DHARCHULA
FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK
DHARCHULA, DISTRICT PITHORAGARH

		Design of Apron		
1	Velocity	(v)	=	14.15 m/Sec
2	Angle of repose of protection material	(ϕ)	=	30°
3	Angle of sloping bank	(θ)	=	26.56°
4	Sin(ϕ)		=	0.50
5	Sin(θ)		=	0.45
6	Specific gravity of Concrete.	Ss	=	2.40
7	Depth of Scour Below RBL (Straight Reach)	(D2)	=	8.23 m
8	Take Depth of Apron Below Bed Level	(D3)	=	1.50 m
9	Remaining Depth -	(D')	D2-D3 =	6.73 m
10	Provide Width of Apron Length of Apron Block Perpendicular to River Flow	1*D'	=	6.73 m

Take	=	6.75 m
------	---	--------

3.0 m Extra Toe Protection By RCC Wall.

11 $(K) = \frac{[1 - \sin^2\theta / 5 \sin^2\phi]}{\%} = 0.447$

12 $(W_{req}) = \frac{0.02323 \cdot V^4}{k(Ss-1)^2} = \frac{186460.93}{1.23} = 151594.25 \text{ Kg}$

(Wreq) = 151.59	tonne
-----------------	-------

Adopted Size of Apron -

Grade of Apron Block		CC M15
NO. Of Apron Provide in Front of Wall	(N)	1.00 m
Length of Apron Block Perpendicular to River Flow	(L)	6.75 m
Width of Apron Block	(B)	6.25 m
Height of Apron Block	(H)	1.50 m
Volume of Apron Block	(V)	63.28 Cum
Density of Apron CC Block		2.40 t/Cum
Weight of Apron Block	(W)	151.87 Tonne

(W) > (Wreq)

Provide 1 no Apron of size 6.75x6.25x1.5m in front of wall.

IRRIGATION DIVISION DHARCHULA
FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP - I IN BLOCK
DHARCHULA ,DISTRICT PITHORAGARH

	Design of Stud		
1 Velocity	(v)	=	14.15 m/Sec
2 angle of repose of protection material	(ϕ)	=	30 °
3 angle of sloping bank	(θ)	=	26.56 °
4 Sin(ϕ)		=	0.50
5 Sin(θ)		=	0.45
6 specific gravity of Concrete,	S _c	=	2.40

Adopted Size of Additional Block:

Width of Flow	(B)	=	60.00 m
Length of Additional Block perpendicular to River Flow		=	Should not exceed 1/5 th of width of flow
		=	1/5 x 60.00
		=	12.00 m
Adopted		=	6.00 m

C/C Spacing of Additional Block in Front of wall = 2 to 5 times of effective length of Stud

		=	12.00 to 30.00
Adopted		=	20.00 m

Grade of Additional Block		=	CC M15
Length of Additional Block perpendicular to River Flow		=	5.75 m
Width of Additional Block		=	5.50 m
Height of Additional Block		=	2.00 m
Volume of Additional Block		=	63.25 Cum
Density of Additional Block		=	2.40 t/Cum
Weight of Additional Block (W)		=	151.80 Tonne
	(W)	>	(W _{req})

Provide CC M15 Additional Block of size 5.75x5.5x2m in front of wall C/C20 m.

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK DHARCHULA ,DISTRICT PITHORAGARH


SILT FACTOR

1.0	Name of Laboratory	Irrigation Division Dharchula
2.0	Name of River/Nala	Kali River
3.0	Type of Sample	Mixture of Aggregate & Sand
4.0	Name of Test	Seive Analysis
5.0	Quantity of Sample	10 kg
6.0	Date of Testing Sample	1-03-2022
7.0	Name of Site	ARMY CAMP-1


DETAIL OF MEASUREMENT				SILT FACTOR ESTIMATION		
S.N.	Seive Size	Weight Retain	Remarks	Mean dia of particle, di	pi	Σ (pi x di)
1.00	80 mm	0.690	-	80.00	0.69	55.20
2.00	63 mm	1.505	-	63.00	1.51	94.82
3.00	40 mm	0.844	-	40.00	0.84	33.76
4.00	20 mm	2.559	-	20.00	2.56	51.18
5.00	16 mm	0.335	-	16.00	0.34	5.36
6.00	12.50 mm	0.355	-	12.50	0.36	4.44
7.00	10 mm	0.330	-	10.00	0.33	3.30
8.00	4.75 mm	0.180	-	4.75	0.18	0.86
9.00	2.36 mm	0.240	-	2.36	0.24	0.57
10.00	1.18 mm	0.106	-	1.18	0.11	0.13
11.00	Balance	2.860	-	-	-	-
	Total	10.00			7.14	249.60

$$d_m = \frac{\sum(\pi_i \times d_i)}{\sum \pi_i} = 34.94$$

$$\text{Silt Factor} = 1.76 \times (d_m)^{0.5} = 10.40$$


JE/AAE
I.D. Dharchula



Assistant Engineer
I.D. Dharchula


Executive Engineer
I.D. Dharchula

STABILITY ANALYSIS OF 8.5 M HIGH RETAINING WALL

Design For Wall

h1=	2	m
h2=	6.5	m
H= h1 + h2	8.5	m
top wid. of fill, X = b1	0	m
b2=	5	m
b3=	0	m
B=	5	m
top width of wall, b=	0.6	m



Let,	
$\gamma(t/m^3)=$	2.0
Angle of repose of soil, $\Phi(\text{deg})=$	37
Coefficient of earth pressure, $K_a = \cos \alpha$	0.25
$\times \left[\frac{\cos \alpha - \sqrt{\cos^2 \alpha - \cos^2 \Phi}}{\cos \alpha + \sqrt{\cos^2 \alpha - \cos^2 \Phi}} \right]$	

unit weight of wall, $\gamma_w(t/m^3)=$ 2.40

Forces:

Horizontal component of earth pressure, $P_h =$ 17.96 at 2.83 from toe
 $P_h = 0.5 \times K_a \times \gamma \times \cos \alpha \times H^2$

Vertical component of earth pressure, $P_v =$ 0.00 at 5 from toe
 $P_v = P_h \tan \alpha$

Assistant Engineer
I.D. Dharchula

Executive Engineer
I.D. Dharchula

STABILITY ANALYSIS OF 8.5 M HIGH RETAINING WALL

CALCULATION OF VERTICAL FORCES & MOMENTS

Sl.No.	Description	Vertical forces, V	Lever arm w.r.t. toe,	Moment(t.m), M
1	Weight of the base = $h_1 \times B \times \gamma_c \times B/2$	24.00	2.50	60.00
2	Weight of the wall over base, $a \times b \times h_2 \times \gamma_w \times (b_2 + b_3) - b/2$	9.36	4.70	43.99
b	$0.5 \times (b_2 - b) \times h_2 \times \gamma_w \times (b_3 + (b_2 - b) \times 2/3)$	34.32	2.93	100.67
3	Weight of the soil above heel $a \times b_1 \times h_2 \times \gamma \times (B - b_1/2)$	0.00	5.00	0.00
4	Vertical component of earth pressure, $P_v =$	0.00	5.00	0.00
	Total, $\sum V$	67.68	$\sum M$	204.66

Safety against sliding-

$$F.O.S = \mu \times \sum V / Ph$$

FOS=

3.01 > 1.5

Safety against Overturning-

$$F.O.S = \sum M / Ph \times L.A$$

FOS=

4.02 > 2

Foundation stability-

$$\text{Total moment about toe, } \sum M_h = \sum M - Ph \times L.A$$

153.78

$$\text{vertical load, } \sum V =$$

67.68

$$\text{eccentricity of vertical load, } e = B/2 - (\sum M_h / \sum V) < B/6$$

0.228 <


0.833


$$P_{max} = (1 + 6e/b) \times (\sum V/B)$$

17.24 < bearing capacity (20 t/m²)


$$P_{min} = (1 - 6e/b) \times (\sum V/B)$$

9.83 safe if positive


Assistant Engineer
I.D.Dharchula


Executive Engineer
I.D.Dharchula

Proposed work Section at "Army Camp-1"



Typical X-Sec of Proposed Work

(All dimensions are in meter except where mentioned otherwise)

जनपद पिथौरागढ़ के धारचूला विकास खण्ड में काली नदी के दाँये पार्श्व में स्थित आर्मी कैम्प-1 की काली नदी से सुरक्षा हेतु बाढ़ सुरक्षा योजना लागत ₹0 2451.07 लाख (₹0 चौबीस करोड़ इक्यावन लाख सात हजार मात्र) को लेखाशीर्षक 8443 डिपॉजिट मद के अन्तर्गत तकनीकी स्वीकृति निम्न प्रतिबन्धों के साथ एतद्वारा प्रदान की जाती है।

01. योजना के क्रियान्वयन के समय डिपॉजिट मद की गार्ड लाईन व निदिष्टियों का पालन करते हुए आवंटित बजट का उपयोग भारतीय सैन्य विभाग के पत्र सं० 1189/Kali River Dated 06.03. 2024 के अनुसार किया जाये।
02. स्वीकृति योजना में प्राविधानित राशि से किसी भी दशा में व्ययविवेक्य न हो।
03. स्वीकृति योजना के स्वरूप में किसी भी प्रकार के फेरबदल से पहले आवश्यक स्वीकृति प्राप्त कर लें।
04. कार्य की गुणवत्ता एवं समयबद्धता हेतु संबंधित अधिशासी अभियन्ता पूर्ण उत्तरदायी होंगे।
05. योजना में ली गई कार्यों की दरों हेतु सम्बन्धित अधीक्षण अभियन्ता उत्तरदायी होंगे।

उपरोक्त स्वीकृति इस कार्यालय के प्राक्कलन पत्रिका के क्रमांक-04/सीई(स्तर-1)/वर्ष 2024-25 में पंजीकृत की जाती है।



(पन्द्रशेखर सिंह)

मुख्य अभियन्ता(स्तर-2)

IRRIGATION DIVISION DHARCHULA


**FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -I IN
BLOCK DHARCHULA DISTRICT PITHORAGARH.**

GENERAL ABSTRACT OF COST

SL.N.	NAME OF ITEM	AMOUNT
		Rs. Lacs
1	A - PRELIMINARY @ 0.50% Of C-Works je Rs-2282.95 ^{1970.49} Lacs	9.85
2	B - LAND	-
3	C - WORK	1970.49
4	L - EARTH WORK	0.00
5	M- PLANTATION L.S.	0.13
6	O - MISCELLANEOUS As per statement attached	3.20
7	P - MAINTENANCE	-
8	E - T & P and WORK CHARGE ESTABLISHMENT @ 0.50% Of C-Works	9.85
9	K - BUILDING @ 0.50% Of C-Works	9.85
10	Contingency including quality control @ 4.00% Of C-Works	78.82
11	G.S.T @ 18.00% Of C-Works	368.88
	TOTAL	2451.07
	Say Rs.Lac	2451.07

Checked
[Signature]


Assistant Engineer
I.D. Dharchula


Executive Engineer
I.D. Dharchula

IRRIGATION DIVISION DHARCHULA


**FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY
CAMP - I IN BLOCK DHARCHULA, DISTRICT PITHORAGARH**

ABSTRACT OF QUANTITIES OF Q-MISC

S.No.	Name of Items	L	B	H	QTY.	UNIT
1	Jeep Journey	*	*	-	1600	km,
2	S/F Sign Boards	-	-	-	2	Nos.
3	Site store	-	*	-	1	Nos.
4	Making Gauge	*	*	-	2	Nos.

ABSTRACT OF COST OF Q-MISC.

S.No.	Name of Items	Unit	Qty.	Rate Rs./Unit	Amount Rs.
1	Jeep Journey	km.	3600	14	50400
2	S/F Sign Boards	Nos.	2	10000	20000
3	Site store	Nos.	1	250000	250000
4	Making Gauge	Nos.	0	3000	0
Total					320400
Say Rs.Lacs					3.2


Assistant Engineer
LD, Dharchula


Executive Engineer
LD, Dharchula

IRRIGATION DIVISION DHARCHULA

FLOOD PROTECTION WORK ALONG RIGHT BANK OF KALI RIVER AT ARMY CAMP -1 IN BLOCK DHARCHULA, DISTRICT PITHORAGARH

DETAILS OF MEASUREMENTS

SNO.	NAME OF ITEMS	NOS	LENGTH	BREADTH	HT/DEPTH	CONTENTS	TOTAL
1	Excavation of river bed material in Hilly area for foundation of Retaining wall/ Gravity wall by mechanical means without using Dozer including cutting and trimming of side slopes and disposing/ backfilling & levelling of excavated material with lead upto 1000 m as per technical specification and direction of Engineer-in charge.					CUM	24766
	i) Retaining Wall Right Bank		1	580.00	(5.3+5.6)	3.50	11063.50
	ii) Apron of C.C. Block		1.00	580.00	6.75	3.50	13702.50
						Total	24766.00
2	Providing concrete for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 10 (Nominal mix 1:3:6)					CUM	436
	a) Wall Right Bank		58	10.00	5.00	0.15	435.00
						Total	435.00
3	Providing concrete for plain concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20					CUM	16356
	i) For Foundation		58	10.00	5.00	2.00	5800.00
	ii) For P/Wall		58	10.00	(5.0+0.6)/2	6.50	10556
						Total	16356.00
4	Providing and laying of apron with cement concrete blocks of size as per Table 1300.1 cast-in-situ and made with nominal mix of M-15 grade cement concrete as per drawing and technical specifications Clause 1301					CUM	7783
	i) Apron		93	6.25	6.75	1.50	5885.16
	iv) Stud 20 m C/C		30	5.50	5.75	2.00	1897.50
						Total	7782.66
5	Providing weep holes in stone masonry wall with 100 mm dia PVC pipe extending through the full width of the wall with slope of 1H:20V towards drawing face complete as per drawing and technical specifications.					RM	3580
	i) 1st Layer C/C 1.5 m		58	6.67	3.98		1539.70
	ii) 2nd Layer C/C 3.0 m		58	5.67	2.97		978.71
	iii) 3rd Layer C/C 4.5 m		58	6.67	1.95		754.38
	iv) 4th Layer C/C 6.0 m		58	5.67	0.94		309.13
						Total	3679.92
6	Providing and laying Expansion joints using 6 mm thick and 6*4 foot size plywood as per drawing and direction of engineer in charge including cost of material, labour and T& P required for proper completion of work.					SQM	3409
	i) Wall		57		5.00	2.00	570.00
	ii) Wall Stem		57		(5.0+0.6)/2	6.50	1037.40
	iii) Apron		1	580.00		1.50	870.00
			92.00		6.75	1.50	931.50
						Total	3408.90

ASD
APB

ASD